



ORISSA POWER GENERATION CORPORATION LIMITED
IB THERMAL POWER STATION
At/PO: BANHARPALI, DIST: JHARSUGUDA – 768 234 (ORISSA)
TELEFAX: (06645) 289 317, Email: contract@opgc.co.in

NOTICE INVITING EXPRESSION OF INTEREST

EOI No .ITPS/CC-22/2011/12

Date: 30/09/2011

Sealed offers are invited from interested & reputed registered Firm / Companies having online experience, Provident Fund Registration Certificate, Service Tax Registration Certificate, valid Income Tax PAN and VAT/Sales Tax Registration Certificate for "**Providing Scaffolding Services at IBTPS in the Main Plant area, CHP and Chimney during the Unit Outage**".

The EOI should contain the commercial offer for final discussion & negotiation to finalize the contract for scaffolding. Bidder should submit the Offers for (i) Providing Scaffolding service along with material. (ii) Providing scaffolding Service without material.

Date of submission: 19/10/2011 up to 2:30PM, Date of Opening: 19/10/2011 at 3:00PM.

For detail information; please visit to our website "www.opgc.co.in"

Sd/- Chief Manager (PSM)-Purchase Contracts (Mob.9338715424)

SAFE & CLEAN POWER IS OUR COMMITMENT

Format for RFQ to be submitted by the agencies:

Sl. No.	Scaffolding service with description/specification of material	Qty.	Rate(Rs.)/Cum
01	With material : MS pipes, MS clamps, gratings, toe guards coir Rope etc.	As per requirement	
02	With material : Cuplock scaffolding with materials	As per requirement	
03	Without material: Material description Not Required	As per requirement	

Applicable taxes must be clearly mentioned in the quotation.

1. **Scope of work:**

- a) The Agency shall Supply, Erect, Modify & Dismantle the Scaffolding as and when required as per the instruction of OPGC Engg. or Supervisor as per IS-1570..
 - b) Scaffolding materials should be strictly MS pipe (tube) conforming to IS-1161 and couplers (Cuplock /Right Angle couplers/Swivel couplers) conforming to IS-1570. The Platform for Scaffolding should be provided with toe boards (300 mmX500 mm or 1200 sq cm) in order to prevent falling. Earth connection points are to be provided in case of Electric Power needs to pass through the scaffolding.
 - c) The Agency should have a Competent Person with high degree of supervising skills of Erection, Modification & Dismantling of Scaffolding.
 - d) The agency should replace instantly defective Scaffolding if any found during the course of work.
 - e) OPGC will provide the detail planning of Scaffolding erection to the agency prior to the outage work.
 - f) The Agency should take care of all housekeeping activity during and after completion of work.
2. Agency shall take back his materials after the completion of work.
3. Tentative period of outage work shall be for **15-20days**.
4. Tentative quantity of job shall be around **3000Cum**.
5. While submitting the RFQ, the agency should see that the cost of PPEs is included in the quotation. Once the quotation is submitted, there shall be no consideration for the cost of PPEs during the entire tenure of contract. OPGC gives safety No.1 Priority at all its areas/sites. All the agencies shall abide by the Safety, Health & Environment Guide Lines for contractors of OPGC. They are to use all required PPEs while working at site. **Minimum required PPEs:** - Safety Shoes, Safety Helmet, Safety Glass, Ear Plug, hand gloves, Nose masks, Safety belts during working at height.
