

BOQ & Price Bid Format
RCC Flooring at TP-11,TP-12, CRH & TP-14 at CHP-II

Sl. No.	Item Description	UOM	Qty.	Unit Rate	Amount
1	Earth Excavation in Ordinary Soil: Earth work in excavation up to 1.5m depth in ordinary soil including dressing & levelling the bed & depositing the excavated materials within 50m. initial lead & 1.5m. initial lift with all cost, conveyance, tools & plants, labour, complete as per the direction of EIC.	CUM	535		
2	Back filling / plinth filling with excavated earth within 50m lead: Earth work in back filling of foundation/ pits / trenches etc including dressing & levelling with excavated earth within initial lead of 50 meters with all costs, conveyance, T&P, labour complete as per the direction of Engg.-in-charge.	CUM	20.5		
3	Supply & Filling Sand: Supplying and Filling of sand in foundation and plinth, watering and ramming including all cost, conveyance, T & P, royalty and labour charges etc. complete as per direction of Engineer-in-charge.	CUM	266.5		
4	PCC (1 : 4 : 8) , 40 mm graded : Cement Concrete(1:4:8) by using 40mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials, scaffolding & labour charges etc. complete as per direction of Engg.	CUM	110		
5	RCC (1 : 1.5 : 3) , 12 to 20 mm Graded HG Chips: Reinforced cement concrete(1:1.5:3) for all type of work using 12 to 20mm graded hard granite crusher broken chips including all cost, laying of concrete, watering, curing, conveyance, T & P, royalties of all materials required for the work, Scaffolding & labour charges etc complete as per the direction of Engineer-in-charge. Reinforcement rod and centering and shuttering will be paid separately.	CUM	160		
6	Centering and shuttering work (Form work) - Mass Concrete / precast slab: Providing and fixing strong, rigid, smooth, levelled, and plumbed CENTERING AND SHUTTERING (Form work) including dismantling the same after the required intervals from the date of casting including cost of all materials, labour, conveyance, loading and unloading, royalties, scaffolding, sundries, tools and plants, etc., complete as per the direction of the Engineer-in-charge - for RCC Foundation and Footing bases of column, mass concrete, precast slabs etc.	Sq.m	82		
7	M.S. Reinforcement bar cutting, binding and placing: Straightening, cutting, bending, binding, tying and placing of M.S. Reinforcement bars (Plain or Tor) in position including all cost of M.S. Reinforcement bars & binding wire (20 to 22 gauge), conveyance, T & P, Scaffoldings, labour charges etc. complete as per direction of EIC.	QNTL	19.4		
TOTAL VALUE IN INR (EXCLUDING GST)					
GST EXTRA AT ACTUALS					